

Addendum #1

Request for Proposal

For

Lower and Upper Arden Dams - Rock Anchor Design

In Central Frontenac



— Quinte —
CONSERVATION

November 13, 2024

Addendum #1

This addendum has been issued prior to the closing date to provide revisions, clarification or supplemental terms or conditions. All revisions, clarifications or supplemental terms or conditions forms part of the request for proposal and amends the original request for proposal documents.

The effects of this addendum shall be included in the proposal price.

All submitted proposals are required to acknowledge in a prominent location that ALL addendums have been fully accounted for.

Available Data

The available data can be found at the below link.

[Arden Dams - Anchor Design](#)

Scope of Work

Add the following bulletin.

- At Upper Arden Dam, complete additional core hole investigations to confirm the feasibility of post-tensioned anchors and to determine the need for injection grouting. Submit a memo regarding the existing concrete quality with photos of the cores, information on concrete strength and quality, and recommendations for anchor installation methodology.

Schedule

Proposal Posted for Tender Wednesday, November 6, 2024

Questions Due Thursday, November 21, 2024 @ 1000

Addenda Posted if required Friday, November 22, 2024

Tender Close Wednesday, November 27, 2024 @ 1430

Project Start-up Monday, November 25, 2024

Answers to Questions

1. The anchor style should be determined by the consultant to meet the needs of the design.
2. A pre-construction survey is not required.
3. Testing of the anchors is not required in this proposal and may be considered at a later date.
4. Monitoring is not required in this proposal and may be considered at a later date.